

## LETTER OF ACCEPTANCE

To,  
**Sri/Smt M/s.A.B.Gopalakrishnan**  
**PAN : AHIPG4920C**

Your e-Tender No **WRD/KWA-CE(CR)/TR/11573/2022\_26\_1\_1/1** dated **24-02-2023** for the **DEPOSIT-CSME-Providing water supply service connection to Galaxy Bridgewood at Bund road jn-Kochappilly road,Chilavannoor in Div No 28(old) of Kochi Corporation-Pipeline Work** has been accepted for a quoted amount of **Rs. 397005/- (Rupees Three Lakh Ninety Seven Thousand Five only)** based on rates quoted for **individual items** which is mentioned in the accompanying schedule. You are directed to submit the stamp GRN ID/Stamp paper, Performance Guarantee and Additional Performance Guarantee as mentioned below and execute an agreement and start the work within a week after getting necessary instructions from the **Assistant Engineer(Water Works Section no 2 Vytila)**. The time allowed for executing agreement without fine will be **14 ( Fourteen)** days from the date of issue of letter of acceptance and a further period of **10 ( Ten)**days time will be allowed to execute the agreement after realizing a fine of **Rs. 3970/- ( Three Thousand Nine Hundred and Seventy Only)** .This fine shall be remitted in favour of the Managing Director, Kerala Water Authority, Account No - STSB 701011400000181, District Treasury, Thiruvananthapuram through e-treasury payment gateway.

1. stamp paper required value **RS. 400/- ( Four Hundred Only)** shall be submitted to the Agreement Authority. (subject to govt orders)

2. Before executing the agreement, you should deposit a Performance Guarantee of **3%** of contract value, ie. **Rs. 11910/- (Rupees Eleven Thousand Nine Hundred and Ten only)** and should be submitted within **14 ( Fourteen)** days of receipt of this LOA (Letter of Acceptance) as below.

a) At least **Fifty (50%)** of Performance Guarantee shall be in the form of Treasury Fixed Deposit in the name of Agreement Authority for a period not less than 28 (twenty eight) days after the completion of defect liability period.

b) Balance Performance Guarantee shall be in the form of bank guarantee. Bank Guarantee is to be submitted in the format prescribed by the Employer in the bid document. Bank Guarantee shall be unconditional and it shall be from any Nationalized/ Scheduled Bank/ Kerala Financial Corporation/ District Co-operative Banks, Primary Co-operative Banks, Urban Co-operative Banks or any other forms prescribed in the revised PWD Manual to be submitted before executing agreement and shall be valid till 28 (twenty eight) days after the completion of defect liability of the Work, in approved format. The Bank Guarantee on instalment basis with lesser period of validity shall not be accepted.

3. An Additional Performance Guarantee of **Rs. 129214/- (Rupees One Lakh Twenty Nine Thousand Two Hundred and Fourteen only)** shall be also deposited for unbalanced price in addition to the normal Performance Guarantee in the following form and it should be to be submitted before executing agreement.

a) At least Fifty percent (50%) of Additional Performance Guarantee shall be in the form of Treasury Fixed Deposit in the name of Agreement Authority for a period not less than 28 (twenty eight) days after the completion of the work.

b) Balance Additional Performance Guarantee Treasury shall be in the form of bank guarantee. Bank Guarantee is to be submitted in the format prescribed by the Employer in the bid document. Bank Guarantee shall be unconditional and it shall be from any Nationalized/ Scheduled Bank/ Kerala Financial Corporation/ District Co-operative Banks, Primary Co-operative Banks, Urban Co-operative Banks or any other forms prescribed in the revised PWD Manual and shall be valid till 28(twenty eight) days after the completion of the Work, in approved format. The Bank Guarantee on instalment basis with lesser period of validity shall not be accepted.

OR

a) Full amount of additional performance guarantee shall be accepted in case of guarantees issued by Kerala Financial Corporation

4. In addition to Performance Guarantee and Additional Performance Guarantee, Performance Security Deposit at the rate 2.5% of Bill amount will be deducted from running bills .
5. Solicitor's fee, if any, to be paid to the Law Officers of Government for scrutinising or drawing up of agreements- will be paid and the same recovered from the successful bidder.
6. You are requested to take an Insurance cover for this work for an amount of Rs. **200000 /-** (**Rupees Two Lakh only**) and submit the same within 15 days of Start of work subjected to the provisions provided in the Bid Document. 0.2% of the Contract Amount will be deducted in the event of failure to submit the Insurance to the concerned Authorities as noted above. (The value shall be generally 0.5% of the Contract Value subject to a minimum of Rs. 2.00 lakh and maximum of Rs. 5.00 lakh.).
7. Engineering personnel in addition to other supporting staff as detailed below for tenure of the contract for works supervision shall be employed.  
**A diploma holder (Civil Engineering) with sufficient practical experience.**
8. The Contractor shall enter into a Contract Agreement with the Agreement Authority within 14 Fourteen working days from the date of 'Acceptance of Tender' or within such extended time as may be granted by the Agreement Authority. The date of despatch of Letter of Acceptance through Contractors Portal shall be the date of Acceptance of Tender.
9. In the eventuality of failure to produce the original documents, or submit the performance security, or enter into agreement with the Agreement Authority within the specified time limit, the Bidder shall be debarred in future from participating in all Government Bids for three years and will be recommended for blacklisting by the competent authority. In such cases, the Government may rearrange the work otherwise or get it done departmentally at the risk and the cost of the Bidder and the loss so sustained by the Government can be realized from the Bidder under the Revenue recovery Act or otherwise the Government may decide.
10. The work should be completed in all respects within **3 months** from the date of handing over the site.
11. Defect Liability period will be **6 months 1 year**
12. All the details mentioned above shall be submitted to the Agreement Authority within 14 (fourteen) days from the date of 'Acceptance of Tender' or within such extended time as may be granted by the Agreement Authority.
13. All the terms and conditions of the Notice Inviting tenders and tender shall be binding on the Contractor.

**AJITHKUMAR R(G11921)**  
**Assistant Executive Engineer**

## ACCEPTED SCHEDULE

Name of Work: DEPOSIT-CSME-Providing water supply service connection to Galaxy  
Bridgewood at Bund road jn-Kochappilly road,Chilavannoor in Div No 28(old) of Kochi  
Corporation-Pipeline Work (DSR 2018 with Cost Index 135.59 )

SI No	Description of work	No. or Qty.	Unit	Accepted Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
<b>1</b>	<b>Working Charges</b>					
1.001	15.43.2 - Dismantling manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-Charge:Bituminous road	135.000	sqm	300.00	40500.00	Rupees Forty Zero Thousand Five Hundred Zero Only
1.002	100.1.1 - Excavating trenches of required width for pipes, cables, etc., including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering, etc., and disposing of surplus excavated soil as directed, within a lead of 50m, in all kinds of soil.	135.600	cum	500.00	67800.00	Rupees Sixty Seven Thousand Eight Hundred Zero Only
1.003	100.8.1 - Fencing one side of trenches, 1.50m height with two rows of 10cm plastic caution tape in vertical casuarina pole (girth 15cm to 24cm) fixed at 2m intervals.	163.400	metre	28.00	4575.20	Rupees Four Thousand Five Hundred Seventy Five And Twenty Zero paise Only
1.004	2.16.1 - Close timbering in trenches including strutting, shoring and packing cavities (wherever required) complete (Measurements to be taken of the face area timbered).Depth not exceeding 1.5m	475.200	sqm	70.00	33264.00	Rupees Thirty Three Thousand Two Hundred Sixty Four Only
1.005	100.98.1008 - Engaging Coolie.	6.000	no	878.00	5268.00	Rupees Five Thousand Two Hundred Sixty Eight Only
1.006	100.98.1009 - Engaging Fitter ( grade 1).	2.000	no	1162.00	2324.00	Rupees Two Thousand Three Hundred Twenty Four

SI No	Description of work	No. or Qty.	Unit	Accepted Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
						Only
1.007	100.7.1 - Bailing out water with 5HP engine and pump set including conveyance to the site, erecting, dismantling and taking back of engine and pump, cost of fuel lubricating oil and other stores pay of staff etc., complete.	29.840	Kwh	37.00	1104.08	Rupees One Thousand One Hundred Four And Eight paise Only
1.008	100.98.213 - Supply of PVC Pipe, 6kg/cm2, 90mm Dia.	174.000	metre	230.00	40020.00	Rupees Forty Zero Thousand Zero Twenty Only
1.009	100.98.211 - Supply of PVC Pipe, 6kg/cm2, 63mm Dia.	90.000	metre	111.00	9990.00	Rupees Nine Thousand Nine Hundred Ninety Zero Only
1.010	100.9.8 - Laying uPVC pipes of class 2 to class 6 and specials, lowering to the trenches already made, placing in position aligning the pipeline to the lines and levels and jointing the pipes and specials with solvent cement and testing the pipeline with water to the required test pressure (excluding cost of pipes and specials): 90 mm nominal outside diameter pipes.	174.000	metre	87.00	15138.00	Rupees Fifteen Thousand One Hundred Thirty Eight Only
1.011	100.9.6 - Laying uPVC pipes of class 2 to class 6 and specials, lowering to the trenches already made, placing in position aligning the pipeline to the lines and levels and jointing the pipes and specials with solvent cement and testing the pipeline with water to the required test pressure (excluding cost of pipes and specials): 63 mm nominal outside diameter pipes.	90.000	metre	80.00	7200.00	Rupees Seven Thousand Two Hundred Zero Only
1.012	OD123226/2022-2023 - Interconnecting the 90mm PVC Pipe line to the 315mm HDPE Pipeline by using 300x80mm MS saddle clamp set (size 100mm wide x 8mm thick), 90mm PVC threaded adapter, Elbow etc. supplied by the contractor and placing in position, jointing with solvent cement and testing to the required test pressure, including cost of all	1.000	no	6000.00	6000.00	Rupees Six Thousand Zero Zero Only

SI No	Description of work	No. or Qty.	Unit	Accepted Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	materials,labour charges and hire for tools,etc..complete.					
1.013	OD123227/2022-2023 - Interconnecting the newly laid 90 mm PVC pipe with the Newly laid 63mm Pvc pipe supplied by the contractor and placing in position,jointing with solvent cement and testing to the required test pressure labour charges and hire for tools, specials, etc..complete.	1.000	no	2000.00	2000.00	Rupees Two Thousand Zero Zero Only
1.014	15.60 - Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	48.600	cum	163.00	7921.80	Rupees Seven Thousand Nine Hundred Twenty One And Eighty Zero paise Only
1.015	16.79 - Providing , laying spreading and compacting graded stone aggregate ( size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tipper to site, for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub - base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer - in-Charge.	40.500	cum	1800.00	72900.00	Rupees Seventy Two Thousand Nine Hundred Zero Only
1.016	4.1.5 - Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	20.250	cum	4000.00	81000.00	Rupees Eighty One Thousand Zero Zero Only

The above work awarded to the contractor A.B.Gopalakrishnan,AHIPG4920C, at his quoted rate for individual items at a total accepted PAC 397005( Three Lakh Ninety Seven Thousand Five Only) as per the condition of the contract.

