

Percentage BoQ

Inviting Authority: KERALA WATER AUTHORITY - P.H. DIVISION, THIRUVALLA

Work Name : Deposit Work 2021-22 -District Panchayath,Kottayam- Providing pipe line extension in various wards of Vazhappally Grama Panchayath.
(Project No.909,26,304/22)

Due Date - 05/07/2022

Contract No: RE-E-Tender No.63/2022-23/EE/PH/TVLA

Name of the Bidder/ Bidding: Sajjan Mohananan

ACCEPTED SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Working Charges - Providing pipe line extension of Vettithuruthel Thekke Odetty Kannanpuzha motorthara at Vazhappally Grama Panchayath (Project No.909)					
1.01	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :All kinds of soil	102.000	cum	558.99	57016.98	INR Fifty Seven Thousand & Sixteen and Paise Ninety Eight Only
1.02	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.375	cum	2057.94	771.73	INR Seven Hundred & Seventy One and Paise Seventy Three Only
1.03	Fencing one side of trenches, 1.50 m height with two rows of 10 cm plastic caution tape in vertical casuarina pole (girth 15cm to 24cm) fixed at 2 m intervals.	50.000	metre	28.12	1406.00	INR One Thousand Four Hundred & Six Only